

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38926

APPROVED SCHEDULE - B

E/BTP/BBMP/E-PMT/18/2019-20, Date: 16.11.2019

Improvements to roads and drains at Kalappa layout, Subbanna Beedi, Venugopalaswamy Temple and surrounding area in ward no 10 (Doddabommasandra) Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				N.M.Shiva kumar		
				In Figures		In Words
1	1009.26	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	255.95	258320.10	Rupees Two Hundred Fifty Five and Ninety Five Paise Only
2	117	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5675.82	664070.94	Rupees Five Thousand Six Hundred Seventy Five and Eighty Two Paise Only
3	245.7	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing, main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) etc complete as per specifications and directions of engineer in charge of the work	Cum	6056.29	1488030.45	Rupees Six Thousand Fifty Six and Twenty Nine Paise Only
4	14.74	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	78947.55	1163686.89	Rupees Seventy Eight Thousand Nine Hundred Forty Seven and Fifty Five Paise Only
5	2280	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	398.26	908032.80	Rupees Three Hundred Ninety Eight and Twenty Six Paise Only
6	1560.6	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete 7.5 cms thick etc complete as per specifications and directions of engineer in charge of the work	Sqm	778.73	1215286.04	Rupees Seven Hundred Seventy Eight and Seventy Three Paise Only
7	8490	Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work	m	64.52	547774.80	Rupees Sixty Four and Fifty Two Paise Only
8	52.02	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	6031.81	313774.76	Rupees Six Thousand Thirty One and Eighty One Paise Only

Signature of the Contractor

N. Shiva Kumar 16/10/23

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

Shiva 16/10/23